

Bluegrass Business Park
Upgrade Innovation to Public Standards
Construct Right Turnlane on Georgetown Road
Construction Bid tabs
Plans sealed April 16, 2026

Item No	Description	KYTC Item #	KYTC Spec #	Estimated Quantities	Unit	Unit Price	Total Price
1	Mobilization	2568	110	1	LS	\$37,250	\$37,250
2	Project Sign	n/a	See Note 10	1	EA	\$1,500	\$1,500
4	Construction Entrance	n/a	See Note 11	1	EA	\$3,500	\$3,500
3	Concrete Washout Pit	n/a	See Note 11	1	EA	\$2,000	\$2,000
4	Silt Fence	2701	213	1,520	LF	\$ 1.65	\$2,508
5	Modified Silt Check	2705	See Note 11	2	EA	\$200	\$400
6	Catch Basin Inlet Protection	2705	See Note 11	4	EA	\$600	\$2,400
7	Maintenance of BMP's	n/a	213	1	LS	\$12,000	\$12,000
8	Remove and Replace Light Poles	24705EC	716	5	EA	\$9,000	\$45,000
9	Maintenance of Traffic	2650	112	1	LS	\$55,000	\$55,000
10	Pavement Removal (Innovation Drive)	2091	203	2,000	SY	\$10	\$20,000
11	Pavement Removal (Georgetown Road)	2091	203	930	SY	\$10	\$9,300
12	Earthwork/Subgrade Preparation	2200	204,206	700	CY	\$ 92.50	\$64,750
13	No 2 Stone	78	805	400	TN	\$52	\$20,800
14	Geogrid	5	304	825	SY	\$4	\$3,300
15	Concrete Curb and Gutter, LFUCG Type 1	1810	506	1,020	LF	\$ 38.50	\$39,270
16	Concrete Sidewalk 5'	2720	505	572	SY	\$ 102.50	\$58,630
17	Concrete Entrance Aprons	2723	505	329	SY	\$ 78.50	\$ 25,826.50
18	Handicap Ramp, include tactile warning strip	2720	505	6	EA	\$2,000	\$12,000
		23158ES505					
19	15" RCP	521	701	121	LF	\$135	\$16,335
20	KYTC Catch Basin Type A	1456	710	2	EA	\$12,000	\$24,000

Item No	Description	KYTC Item #	KYTC Spec #	Estimated Quantities	Unit	Unit Price	Total Price
21	KYTC Manhole Type B 4' Diameter	1761	710	1	EA	\$4,000	\$4,000
22	15" Sloped and Flared Headwall	1202	610	1	EA	\$3,000	\$3,000
23	Class II Channel Lining	2483	703	30	TN	\$80	\$2,400
24	6' Perforated Pipe	1001	810	200	LF	\$30	\$6,000
25	Longitudinal Edge Key	21289ED	408	481	LF	\$20	\$9,620
26	Transverse Edge Key	2585	408	37	LF	\$80	\$2,960
27	6" Solid White Stripe	6542	714	960	LF	\$ 1.10	\$1,056
28	6' Solid Yellow Stripe	6543	714	1,930	LF	\$ 1.10	\$2,123
29	Turn Arrows	6574	112	10	EA	\$120	\$1,200
30	Stop Bar	6568	717	115	SF	\$7	\$805
31	Crosswalk 12" Solid White	6566	717	120	LF	\$ 6.25	\$750
32	Edgeline Rumble Strips	2697	717	530	LF	\$0.47	\$249
33	Inlaid Pavement Markers	6610	712	7	EA	\$75.00	\$525
34	Stop Sign	6406	715	27	SF	\$111	\$3,000
Georgetown Road Pavement							
35	1 1/4" Bituminous Surface	339	403	81	TN	\$180	\$14,580
36	1 1/2" Bituminous Base	205	403	97	TN	\$115	\$11,155
37	3 1/2" Bituminous Base	205	403	227	TN	\$115	\$26,105
38	4" Bituminous Base	205	403	191	TN	\$126	\$24,066
39	Dense Graded Aggregate	1	302	600	TN	\$40	\$24,000
Innovation Drive							
40	1 1/2" Bituminous Surface	339	403	170	TN	\$180	\$30,600
41	7 1/2" Bituminous Base	205	403	848	TN	\$115	\$97,520
42	9" Dense Graded Aggregate	1	302	1,063	TN	\$40	\$42,520

