



Burdine Security Group, Inc.

Security Services • Pinkston's Locksmith • Ace Lock & Alarm

LFUCG
200 East Main Street
Lexington, KY

April 9, 2013

RFP #10-2013

Proposal: Replace existing access control system and install new access control on three doors.

Description: Replace existing access control panels, software, and proximity readers with new. The new panels and software will tie into existing system already installed in various locations throughout Lexington, including the Mayor's Office. All existing locking devices will be checked for accuracy and function. A total of 39 doors will have the access control replaced. Install three new proximity readers on the main floor of the government center. The proximity readers and locking devices will be installed on the side interior entrance door, stairwell located near the elevator, and the back door to the Mayor's office.

Materials:

- 16 Access Control Panels
- 7 Expansion Modules
- 1 Power Supply
- 42 Proximity Readers
- 500 Plain White Proximity Cards
- 1 Electronic Strike
- 1 Storeroom Function Leverset
- 1 Magnetic Lock
- 1 Request to Exit Motion Sensor
- 1 Request to Exit Push Button
- 1 Adams Rite Electrified Exit Device
- Cable
- Labor
- Misc. Equip. (connectors, etc.)

Total Installed: \$61,637

Prepared by:

Will Burdine

(859)254-4414 • (859)254-2084 • Fax: (859)254-4415
1408 W. Main Street • Lexington, KY 40517