

LEXINGTON-FAYETTE URBAN COUNTY GOVERNMENT CONTRACT CHANGE ORDER		Date:	February 10, 2017
		Project:	Waste Transfer Station Repair
		Location:	Old Frankfort Pike
To (Contractor): RRC Company, LLC 279 Blackurn Road Cynthiana, KY 41031		Contract No.	45-2016
		Original Contract Amt.	\$412,302.81
		Cumulative Amount of Previous Change Orders	\$0.00
		Percent Change - Previous Change Orders	0.00%
		Total Contract Amount Prior to this Change Order	\$412,302.81
		Change Order No.	#1
		You are hereby requested to comply with the following changes from the contract plans and specification;	
Current Change Order			
Item No.	Description of changes-quantities, unit prices, change in completion date, etc.	Decrease in contract price	Increase in contract price
	See Attached Sheet		
	Total decrease	\$4,050.00	
	Total increase		\$131,255.11
	Net Amount of this Change Order	\$127,205.11	
	New Contract Amount Including this Change Order	\$539,507.92	
	Percent Change - This Change Order		30.85%
	Percent Change - All Change Orders		30.85%
The time provided for the completion in the contract and all provisions of the contract will apply hereto.			
Recommended by <u><i>[Signature]</i></u>		(Proj.Mgr.)	Date <u>2/14/17</u>
Accepted by <u><i>[Signature]</i></u>		(Contractor)	Date <u>2/14/17</u>
Approved by <u><i>[Signature]</i></u>		(Director)	Date <u>2/18/17</u>
Approved by <u><i>[Signature]</i></u>		(Commissioner)	Date <u>2/18/17</u>
Approved by <u><i>[Signature]</i></u>		(Mayor or CAO)	Date <u>16-Mar-2017</u>

**LEXINGTON-FAYETTE URBAN COUNTY GOVERNMENT
CHANGE ORDER**

DATE: February 10, 2017
 Change Order #: #1
 CONTRACT #: 45-2016

Project: Waste Transfer Station Repair

You are hereby requested to comply with the following changes from the contract plans and specifications;

Item No.	ADD / DEL	Description of changes	Units	Quantity	Unit Price	Decrease in contract price	Increase in contract price
1	ADD	Demo. Slab Cutting (12" thick)	LF	105	\$ 7.68	\$ -	\$ 806.40
3	ADD	Demo. Reinf. Concrete (floor)	SF	1,898	\$ 1.17	\$ -	\$ 2,220.66
6	ADD	Concrete (4500psi)	CY	54	\$ 125.05	\$ -	\$ 6,752.70
9	ADD	Epoxy Anchoring Cartridge & Anchor	EA	35	\$ 51.21	\$ -	\$ 1,792.35
11	ADD	Floor, Placing Concrete	CY	54	\$ 31.31	\$ -	\$ 1,690.74
12	ADD	Floor Finishing	SF	1,898	\$ 1.20	\$ -	\$ 2,277.60
13	ADD	Rebar - Floor Slab #8	TON	12	\$ 1,965.38	\$ -	\$ 23,584.56
14	ADD	Dowel into existing slab	EA	70	\$ 9.18	\$ -	\$ 642.60
15	ADD	Drill holes for horiz. & grout dowels	EA	70	\$ 12.91	\$ -	\$ 903.70
16	ADD	Control joints saw & joint filler	LF	100	\$ 10.37	\$ -	\$ 1,037.00
18	ADD	Remove bad soil	CY	141	\$ 23.82	\$ -	\$ 3,358.62
20	ADD	DGA compacted	CY	141	\$ 31.61	\$ -	\$ 4,457.01
25	ADD	Field Welds 1/4"	LF	400	\$ 41.68	\$ -	\$ 16,672.00
29	ADD	Anchor Bolts (Epoxy Type)	EA	100	\$ 7.38	\$ -	\$ 738.00
30	ADD	Misc. Steel Members	LF	1,200	\$ 14.29	\$ -	\$ 17,148.00

LEXINGTON-FAYETTE URBAN COUNTY GOVERNMENT

CHANGE ORDER

DATE:

February 10,2017

Change Order #:

#1

CONTRACT #:

45-2016

Project:


Waste Transfer Station Repair

You are hereby requested to comply with the following changes from the contract plans and specifications;

Item No.	ADD / DEL	Description of changes	Units	Quantity	Unit Price	Decrease in contract price	Increase in contract price
31	ADD	12" dia.concrete filled Bollards	EA	3	\$ 1,786.47	\$ -	\$ 5,359.41
35	DEL	Siding (18 ga.)@bracing	SF	375	\$ 10.80	\$ 4,050.00	\$ -
38	ADD	Install water supply spicket	LS	1	\$ 216.00	\$ -	\$ 216.00
39	ADD	Weld T-bars on 1 1/4" coming from columns	LS	1	\$ 360.00	\$ -	\$ 360.00
40	ADD	Wall saw cutting overtime on Saturday	LS	1	\$ 1,488.00	\$ -	\$ 1,488.00
41	ADD	Price increase for change from DGA to #2 stone	TON	605	\$ 4.80	\$ -	\$ 2,904.00
42	ADD	Demo old push wall, pull wall and girts back in line	LS	1	\$ 4,100.00	\$ -	\$ 4,100.00
43	ADD	Change Steel wall thickness from 1/8" to 3/16"	SF	1,648	\$ 19.87	\$ -	\$ 32,745.76
						\$ 4,050.00	
Total increase							\$ 131,255.11
Net (increase) in contract price							\$ 127,205.11

JUSTIFICATION FOR CHANGE	PROJECT:	Waste Transfer Station Repair
	CONTRACT NO.	45-2016
	CHANGE ORDER:	#1

- Necessity for change: During construction it was discovered that a larger amount of the flooring needed to be replaced. Also during construction it was discovered that the rear push wall had failed and need to be replaced.
- Is proposed change an alternate bid? ___ Yes X No
- Will proposed change alter the physical size of the project? X Yes ___ No
The failure of the push wall has expanded the the scope of the project.
- Effect of this change on other prime contractors: N/A
- Has consent of surety been obtained? ___ Yes X Not Necessary
- Will this change affect expiration or extent of insurance coverage? ___ Yes X No
If "Yes", will the policies be extended? ___ Yes ___ No
- Effect on operation and maintenance costs: N/A
- Effect on contract completion date: Completion Date is extended to May 15, 2017


 _____ Mayor Date 16-Mar-2017