OWNER

O General Services LFUCG

ARCHITECT

O Fitzsimons Office of Architecture

**PROPOSAL REQUEST** 

CONTRACTOR

O Churchill McGee

FIELD OTHER

PROJECT: (name, address) Carver Center Rehabilitation

522 Patterson St.

Lexington, KY

PROPOSAL REQUEST NO: Six

ARCHITECT'S PROJECT NO:

DATE:

July 5, 2013

0

OWNER:

LFUCG

201 East Main St.

Lexington, KY 40508

CONTRACT FOR: General Construction

116-2012

CONTRACT DATED:

2/28/13

TO: (Contractor)

Churchill McGee

1315 - C West Main St.

Lexington, KY 40508

Please submit an itemized quotation for changes in the Contract Sum and/or Time incidental to proposed modifications to the Contract Documents described herein.

THIS IS NOT A CHANGE ORDER NOR A DIRECTION TO PROCEED WITH THE WORK DESCRIBED HEREIN.

Description: (Written description of the Work)


Provide all labor and materials required to demolish the required portions of the areaways that served as air intakes, removing sheet metal ductwork, fill the void with gravel, in-fill concrete block masonry air intake openings with concrete block, form and pour a new concrete cap to seal the area way. Remove existing downspout boot, provide splash block and turn the downspout onto grade to drain away from the building.

Attachments: (list attached documents that support description) SD-4, 5, and 6

ARCHITECT: Fitzsimons Office of Architecture

BY:

Gregory Fitzsimons AIA



#### PARTIAL FLOOR PLANS 1st


FITZSIMONS OFFICE OF ARCHITECTURE, INC. Lexington, KY 10508 112 W. Third Street Tel 853-243-0838 rax 035-226-3203

Partial Floor Plan Carver Community Center Renovation 116-2012


110

Revisions

SD-4




SCALE: 1/8" = 1'-0"




#### PARTIAL FLOOR PLAN basement

FITZSIMONS OFFICE of ARCHITECTURE, INC.

I 12 W. Third Street Lexingfon, KY 10508
Tel 653-215-0838 fax 835-226-3283



SCALE: 1/8" = 1'-0"



SCALE: 1/4" = 1'-0"

#### AREAWAY CAP DETAIL

FITZSIMONS OFFICE OF ARCHITECTURE, INC.

1 1 2 W. Third Street Tel: 853-243-0838 Lexington, KY 10508

Areaway Detail
Carver Community
Center Renovation
116-2012

	Date Project Drawn Checked 6F Reyislons
l	2 5

SD-6

# Churchill McGee, LLC Carver Air Vent Change Order

## 1 General Requirements

142.00 Insurance

143.00 Overhead & Profit 174.19 Dumpster (full size, normal wt.)

15.00% \$1,531.59

2 Existing Conditions
241.13 Select Demolition
100 Existing Air Intake
200 Duct Work
300 Core Drill-Floor & Ext Wall

\$3,000.00

3 Concrete
300.00 Basic Concrete Material

100 infill Existing Air Infake (Rock) 200 New 4" Concrete Cap 300 Forms & WWF

\$2,252.00

## 4 Masonry

400.00 Masonry

100 Intill/Olose existing opening & Repair Brick

100 CMU 200 Worlar 300 Sand

\$789.75

**22 Plumbing**2200.00 Plumbing
100 6" Pipe
200 Fitings

\$3,187.00

# \*\*\*\*EXCLUDES ANY EXTERIOR WALL REPAIRS ONCE EXISTING AIR INTAKE AREAWAYS ARE REMOVED. IT IS ASSUMED THAT THE EXISTING BRICK IS IN SUFFICIENT CONDITION.\*\*\*\*

Project schedule will increase by 7 days (weather pending upon approval)

OWNER

O General Services LFUCG

ARCHITECT

O Fitzsimons Office of Architecture

**PROPOSAL REQUEST** 

CONTRACTOR

O Churchill McGee

FIELD OTHER

Carver Center Rehabilitation

522 Patterson St.

Lexington, KY

PROPOSAL REQUEST NO: Seven

DATE:

August 1, 2013

0

ARCHITECT'S PROJECT NO:

116-2012

OWNER:

PROJECT:

(name, address)

LFUCG

201 East Main St.

Lexington, KY 40508

CONTRACT DATED:

CONTRACT FOR: General Construction

2/28/13

TO: (Contractor)

Churchill McGee

1315 - C West Main St. Lexington, KY 40508

Please submit an itemized quotation for changes in the Contract Sum and/or Time incidental to proposed modifications to the Contract Documents described herein.

THIS IS NOT A CHANGE ORDER NOR A DIRECTION TO PROCEED WITH THE WORK DESCRIBED HEREIN.

Description: (Written description of the Work)

Provide all labor and materials required omit the specified roof insulation and provide a tapered roof system at 1/8" per foot. The tapered insulation system is required due to the existing roof decking being below the adjacent bearing walls.

Attachments: (list attached documents that support description) None.

ARCHITECT: Fitzsimons Office of Architecture

Gregory Fitzsimons AIA

## 7/12/2013

							730.00 <b>Roofing</b>	7 Moisture Protection		143.00 Overhead & Profit	1 General Requirements		
1128	Quantity Unit Material		1 LS	Quantity Unit		•	1	Quantity Unit		\$1,267.50 1 LS	Quantity Unit		
	Material	Bid Cost		Material	Bid Cost			Material	Bid Cost		Material		
	Labor			Labor				Labor			Labor		
	Equipment			Equipment				Equipment			Equipment	Bic	
	Sub			Sub			\$8,450.00	Sub			Sub	Bid Cost	
	Other			Other				Other			Other		
\$0.00	Total		\$0.00	Total			\$8,450.00	Total		\$1,267.50	Total		

# \$9,717.50

Excludes: down spouts, roof drains, ceiling repairs, and masonry work.

Project schedule will increase by 4 days ( weather pending upon approval)

### S D M Contracting, Inc

Change Order #3

PROJECT:

Carver Community Center Renovation 522 Patterson Street Lexington, Ky. 8/7/13

S D M Contracting, Inc. proposes to furnish materials and labor to do the following specification sections:

- 1) Install 1/8" tapered roof insulation over metal deck on roof area with drains.
- 2) All roof drains piping to be removed by others.
- 3) Must have a written change order back from Churchill McGee before work can begin.

Price \$8,450.00

If you should have any questions please feel free to contact me at (859) 552-6039.

Thank you!

Sincerely,

Steven Mitchell S D M Contracting, Inc. President

295 Chilesburg Rd Lexington KY 40509 (859) 552-6039

Fax (859) 264-9151

#### Joyce Thomas

From: Andrew Grunwald

Sent: Tuesday, September 03, 2013 1:12 PM

To: Joyce Thomas

Subject: FW: Carver Community Center - Change Order #3

Ms. Thomas,

Please proceed with execution of Change Order #3.

Andrew Grunwald

From: Goodpaster, Stuart (KYTC-D07) [mailto:Stuart.Goodpaster@ky.gov]

Sent: Tuesday, September 03, 2013 1:11 PM

To: Andrew Grunwald

Subject: RE: Carver Community Center - Change Order #3

#### Mr. Grunwald:

I have reviewed Construction Contract Modification #3 for work being done to Carver Center as part of Environmental Mitigation for the Newtown Pike Extension Project. The work is in accordance with the Record of Decision (FHWA-KY-EIS-03-01-F). We concur with the work. You are authorized to proceed with a Change Order for the work.

If you have further questions, or need additional information please let me know.

#### STUART C. GOODPASTER, P.E.

Transportation Engineer I Newtown Pike Extension Project Manager 763 West New Circle Rd Lexington, KY 40512-0127 Phone: 859-246-2355

Phone: 859-246-2355 Fax: 859-246-2354

eMail: Stuart.Goodpaster@ky.gov

From: Andrew Grunwald [mailto:AGrunwal@lexingtonky.gov]

Sent: Wednesday, August 28, 2013 4:32 PM

To: Goodpaster, Stuart (KYTC-D07)

Subject: Carver Community Center - Change Order #3

Stuart,

Attached for your review and approval is a Construction Contract Modification (CM#3) for the work being done to the Carver Center as part of the Newtown Pike Extension Project. The total cost of CM#3 is \$20,477.84. This will bring the construction cost of the Carver Center Renovation to \$1,121,059.25 (We are still within our budget). The CM contains two items...

1. Demolish areaways, remove ductwork, fill voids w/gravel, infill with masonry block the intake openings, form and pour new concrete cap per Progress Report #6 2. Omit specified roof insulation and provide tapered roof system per Progress Report #7

Review of CM ...

CM#1				\$	3,	655	.85
CM#2				\$	2,	405	.56
CM#3				\$2	20,	477	.84
Total	CM	to	date	\$2	26,	539	.25

Please let me know if you are in agreement with this CM.

Thank you

Andrew Grunwald, P.E. Municipal Engineer Sr. LFUCG - Division of Engineering