



LOCAL PUBLIC AGENCY CHANGE ORDER

Page Sheet 1

Contract ID SC-628-2000001984 Project Sponsor Lexington-Fayette Urban Co. Govt.
 Change Order No 2 County Fayette
 Contractor L-M Asphalt Partners, Ltd., dba Project Number 07-03721.00
 Contractor ATS Construction Project Name Mt Tabor Road Improvments
 Address 3009 Atkinson Ave, Suite 400, Lexington, KY 40509

Proposed Changes in Connection with Contract Items:

Item No.	Description	Quantity	Unit	Unit Price	Amount
	See Attached Sheets				
<i>Total for this Page</i>					
<i>Total for Continuation Page(s)</i>					182,474.10
<i>Total Contract Items</i>					182,474.10

Proposed Items of Supplemental Agreement:

Ref. No.	Description	Quantity	Unit	Unit Price	Amount
<i>Total for this Page</i>					
<i>Total for Continuation Page(s)</i>					
<i>Total Supplemental Agreement</i>					
Total Increase Amount					\$ 182,474.10

Time Extension/Explanation:

[Empty box for Time Extension/Explanation]

Reasons for Proposed Changes and Cost Analysis:

See Attached Sheets

If approved by Transportation Cabinet, the undersigned contractor agrees to do the work outlined herein and to accept as payment in full the basis of payment as set forth herein.

Requested Scott Ballard July 15, 24
Project Engineer DATE

Recommended _____
District LPA Coordinator DATE

Recommended _____
Commissioner of Rural & Municipal Aid DATE

Approved Scott Ballard July 15, 2024
LPA Signature Authority DATE

Municipal Engineer, Senior
Title DATE

Approved _____
Secretary of Transportation Cabinet DATE

ATS Construction
Contractor

By:

[Signature]

7-11-24
Date

Page	Sheet 2		
Contract ID	SC-628-2000001984	Project Sponsor	Lexington-Fayette Urban Co.
Change Order No	2	County	Fayette
Contractor	L-M Asphalt Partners, Ltd., dba	Project Number	07-03721.00
Contractor	ATS Construction	Project Name	Mt Tabor Road Improven
Address	3009 Atkinson Ave, Suite 400, Lexington, KY 40509		

No.		Description	Quantity	Unit	Unit Price	Amount
2	DEL	QUAL CONT SERVICES - ALLOWANCE	-0.770	LS	10,000.00	-7,698.75
6	ADD	REMOVE AND REPLACE 6FT WOODEN FENCE	102.000	LF	57.00	5,814.00
7	DEL	REMOVE AND REPLACE WOOD PLANK FENCE	-412.000	LF	57.00	-23,484.00
9	DEL	DENSE GRADE AGGREGATE	-4,091.740	TN	18.00	-73,651.32
10	ADD	NO.2 STONE	1,841.780	TN	36.00	66,304.08
11	ADD	NO.57 STONE	63.640	TN	50.00	3,182.00
12	DEL	FORMED CLASS A CONC & UNFINISHD CONC	-1.000	CY	625.00	-625.00
13	ADD	SIDEWALK 4 1/2" CONCRETE	92.530	SY	70.00	6,477.10
14	ADD	8" CONCRETE ENTRANCE PAVEMENT	216.260	SY	90.00	19,463.40
15	DEL	SIDEWALK RAMPS	-19.300	SY	120.00	-2,316.00
16	DEL	LFUCG CONCRETE CURB&GUTTER, TYPE 1	-73.000	LF	23.30	-1,700.90
17	ADD	BITUMINOUS BASE	1,054.750	TN	125.00	131,843.75
18	DEL	CLASS I BITUMINOUS SURFACE	-30.210	TN	125.00	-3,776.25
20	DEL	LFUCG CURB BOX INLET - TYPE A	-2.000	EA	7,825.00	-15,650.00
21	ADD	LFUCG CURB BOX INLET - TYPE D	1.000	EA	5,400.00	5,400.00
22	DEL	ADJUST MANHOLE	-2.000	EA	3,500.00	-7,000.00
25	ADD	12" PVC PIPE	32.000	LF	175.00	5,600.00
27	ADD	SOD/FERT/LIMESTONE APPLICATION	690.000	SY	14.95	10,315.50
28	DEL	4" HDPE UNDERDRAIN PIPE	-22.000	LF	11.50	-253.00
29	DEL	TEMPORARY SILT FENCE	-561.000	LF	2.00	-1,122.00
30	DEL	STORM DRAIN INLET PROT - SILT TRAP, TYP C	-13.000	EA	0.01	-0.13
31	DEL	EDGE KEY	-7.000	LF	22.00	-154.00
32	ADD	PRECAST MODULAR BLOCK RETAINING WALL	37.130	SF	47.50	1,763.68
33	DEL	PROJECT SIGN	-2.000	EA	500.00	-1,000.00
35	DEL	42" HIGH STEEL HANDRAIL W/PICKETS	-3.000	LF	186.00	-558.00
<i>Total for this Page</i>						117,174.16

Reasons for Proposed Changes and Cost analysis:

2, 6: Final quantity adjustment.

7 & 62: Since the design of the project the property owner replaced the wooden fence with vinyl fencing. This change order is to replace-in-kind the vinyl fence that was removed and will be replaced.

16, 21 & 25: Correcting street drainage issue.

9 - 35: Final quantity adjustment.

Page	Sheet 3		
Contract ID	SC-628-2000001984	Project Sponsor	Lexington-Fayette Urban Co.
Change Order No	2	County	Fayette
Contractor	L-M Asphalt Partners, Ltd., dba	Project Number	07-03721.00
Contractor	ATS Construction	Project Name	Mt Tabor Road Improven
Address	3009 Atkinson Ave, Suite 400, Lexington, KY 40509		

No.		Description	Quantity	Unit	Unit Price	Amount
36	ADD	IMBEDDED DETECT WARNINGS - INSTALL	10.000	SF	18.00	180.00
37	ADD	BROKEN WHITE LINE 6 IN (2FT SEG, 6FT SKIP)	-528.000	LF	6.00	-3,168.00
38	DEL	DOTTED WHITE LINE - 4 IN (3FT SEG, 8 FT SKIP)	-231.000	LF	6.00	-1,386.00
39	DEL	LANE LINE WHITE - 4 IN THERMO	2,101.000	LF	2.00	4,202.00
40	ADD	LANE LINE YELLOW - 4 IN THERMO	2,845.000	LF	2.00	5,690.00
41	DEL	SOLID YELLO LINE - DOUBLE 4 IN THERMO	-1,053.000	LF	4.00	-4,212.00
42	DEL	PAVE MARKING THERMO ENHANCED X-WALK	-65.000	SF	6.50	-422.50
43	DEL	PAVE STRIPING PERM THERMO 6 IN WHITE	-2,510.000	LF	2.00	-5,020.00
44	ADD	PAVE MARKING - THERMO BICYCLE SYMBOL	1.000	EA	250.00	250.00
45	ADD	PAVE MARK - PREF THERMO CRVED ARROW	1.000	EA	120.00	120.00
46	DEL	PAVE MARKING - THERMO "ONLY"	-1.000	EA	300.00	-300.00
47	DEL	PAVE MARKING - THERMO STOP BAR 24 IN	19.000	LF	10.00	190.00
49	ADD	4FT TEMP CONSTRUCTION SAFETY FENCE	561.000	LF	8.68	4,869.48
50	ADD	CONDUIT 2" (RIGID STEEL)	38.000	LF	20.00	760.00
51	DEL	CONDUIT 2" (SCHEDULE 40 PVC)	-285.000	LF	12.50	-3,562.50
52	DEL	ELECTRICAL JUNCTION BOX	-3.000	EA	1,750.00	-5,250.00
56	DEL	ADDITIONAL 2" PVC SCH 40	-50.000	LF	12.50	-625.00
57	DEL	COUPLING, CONDUIT, PVC 2"	-4.000	EA	40.00	-160.00
58	ADD	PAVE MARKER V - BIDIRECTIONAL YELLOW	6.000	EA	100.00	600.00
61	DEL	PERFORMANCE AND PAYMENT BONDS	-0.254	LS	8,750.00	-2,225.64
62	ADD	Remove and Replace White Vinyl 3 Plank Fence	416.000	LF	67.80	28,204.80
63	ADD	Change CBI Type A to CBI Type B	2.000	EA	8,325.00	16,650.00
64	ADD	Modified Header Curb	204.000	LF	42.00	8,568.00
65	ADD	Mass Concrete	14.000	CY	307.00	4,298.00
66	ADD	SEED AND STRAW	1.000	LS	262.50	262.50
<i>Total for this Page</i>						48,513.14

Reasons for Proposed Changes and Cost analysis:

36-61: Final quantity adjustment.

63: This was a field change to the drainage design to accommodate excessive pipe skew angles both in the proposed and existing drainage systems.

64: To fix an adverse final grade condition along Mt Tabor Rd that would have caused the loss of four trees and impacted an existing water meter vault and undermined a utility pole.

65: Mass Concrete to provide a "cap" on the newly constructed retaining walls.

66: Final quantity adjustment.

Page Sheet 4

Contract ID	SC-628-2000001984	Project Sponsor	Lexington-Fayette Urban Co.
Change Order No	2	County	Fayette
Contractor	L-M Asphalt Partners, Ltd., dba	Project Number	07-03721.00
Contractor	ATS Construction	Project Name	Mt Tabor Road Improven
Address	3009 Atkinson Ave, Suite 400, Lexington, KY 40509		

No.		Description	Quantity	Unit	Unit Price	Amount
67	ADD	MILLING	58.350	TN	28.00	1,633.80
68	ADD	LIGHT POLE BASE RELOCATE	1.000	EA	5,145.00	5,145.00
69	ADD	DRAINAGE CHANGE AT GRIBBIN	1.000	EA	5,500.00	5,500.00
70	DEL	REIMBURSEMENT - WORK PAID FOR BUT NOT PERFORMED ITEM 8 "REMOVE & REPLACE WOODEN PICKET FENCE"	-106.000	LF	57.00	-6,042.00
71	ADD	REMOVE CURB AND GUTTER	32.000	LF	20.00	640.00
72	ADD	SEEDING AND PROTECTION	30.000	SY	4.00	120.00
73	ADD	REMOVE SIDEWALK	7.000	SY	100.00	700.00
74	ADD	SIDEWALK RAMPS	7.000	SY	70.00	490.00
75	ADD	CORED HOLE DRAINAGE BOX	1.000	EA	600.00	600.00
76	ADD	MOBILIZATION	1.000	LS	4,000.00	4,000.00
77	ADD	MAINTAIN AND CONTROL TRAFFIC	1.000	LS	2,500.00	2,500.00
78	ADD	STAKING	1.000	LS	1,500.00	1,500.00
<i>Total for this Page</i>						16,786.80

Reasons for Proposed Changes and Cost analysis:

67: Final quantity adjustment.

68: Relocating a street light.

69: Modification of curb to provide street drainage.

70: Work not performed.

71-78: Correcting street drainage issue.