HCI HERRICK COMPANY, INC

780 Enterprise Dr.
Lexington, KY 40510
tel: (502) 839-3484
fax: (502) 839-0939
www.herrick-company.com

June 8, 2026

Strand Associates, Inc.
651 Perimeter Drive, Suite 220
Lexington, KY 40517

Attention: Ms. Liz Dienst, PE

RE: Lexington-Fayette Urban County Government
Town Branch & West Hickman WWTPs
UV Disinfection Process Replacement Project
COP-16: Credit for Generator Fuel Piping

Dear Ms. Dienst,

At the Owner's request, the installation and startup of the new fuel transfer pumps and associated fuel system equipment have been removed from the project scope.

Herrick Company coordinated with Cummins regarding the possibility of returning the fuel pumps for credit. Cummins advised that the pump manufacturer would not accept the pumps for return because they were custom-fabricated specifically for this project. As a result, the pumps will be turned over to the Owner.

The credit associated with this change consists of the deleted installation labor, deleted installation materials, and the Cummins startup and commissioning costs that are no longer required.

We propose to perform the work contained in the above for a **lump sum credit of <$1,998.00>.** A detailed breakdown of our proposal is provided below. We hope that you find this proposal acceptable. Should you have any questions or need any additional information, please do not hesitate to contact me.

Labor	($348.00)
Materials	($150.00)
Startup/Commissioning Credit	($1,500.00)
Total Credit	**($1,998.00)**

Sincerely,

Jonah Donze
Project Manager

cc: Luke Zakrzewski, PE – HCI
Cody Lokits, PE - HCI
Mike Davis, PE – Strand
Emily Epperson, PE – LFUCG

HCI
HERRICK
COMPANY, INC

780 Enterprise Dr.
Lexington, KY 40510
tel: (502) 839-3484
fax: (502) 839-0939
www.herrick-company.com

August 11, 2026

Strand Associates, Inc.
651 Perimeter Drive, Suite 220
Lexington, KY 40517

Attention: Ms. Liz Dienst, PE

RE: Lexington-Fayette Urban County Government
Town Branch & West Hickman WWTPs
UV Disinfection Process Replacement Project
COP-18: NPW Demolition West Hickman WWTP

Dear Ms. Dienst,

As requested by LFUCG via marked up drawings in COP-18, please see the attached proposal to perform demolition and disposal of select NPW piping components within Building 11 and 14 at West Hickman WWTP. A detailed scope of our proposal is as follows:

1. Demolition and disposal of existing 12" NPW piping from a wall flange at the southwest corner of Building 11 to a 20" x 12" tee connection. Demolition to include two 12" blind flanges, flange hardware/gaskets, and removal/patching of existing hangers/supports as necessary. Disposed materials to be removed through an existing access hatch in the vicinity with boom truck for hoisting.
2. Demolition and disposal of existing 12" NPW piping and appurtenances within Building 14 to include:
    a. Dechlorination Water Supply Pumps (2 each)
    b. Strainer
    c. Strainer Backwash Pump & Piping
    d. PVC Dilution Water Piping (PVC)
3. Demolition to include all concrete breaking and removal of all pump pads (x3) and concrete pipe supports (x4). Concrete floors to be skim coated and restored to flat/patched condition upon removal of concrete.
4. Disposed materials to be removed through an existing access hatch in the vicinity with boom truck/crane for hoisting.
5. Electrical demolition and make safe of strainer backwash pump, dechlorination pumps, and strainer including demo of power and control wiring, control panel, and disconnects are also included. Re-labeling of MCC breakers to spare and capping of existing embed conduit is included.

We propose to perform the work contained in the above for a **lump sum price of $54,000.00.** A detailed breakdown of our proposal is provided below. We hope that you find this proposal acceptable. Should you have any questions or need any additional information, please do not hesitate to contact me.

Labor/Labor Burden	$23,800.00
Materials/Other	$8,050.00
Subcontractors	$3,000.00
Equipment/Fuel	$7,225.00
Bonds/Insurance	$1,250.00
Overhead & Profit	$10,675.00
Total	**$54,000.00**

Sincerely,

Jonah Donze
Project Manager

cc: Cody Lokits, PE - HCI
Mike Davis, PE – Strand
Emily Epperson, PE – LFUCG

HCI HERRICK COMPANY, INC

780 Enterprise Dr.
Lexington, KY 40510
tel: (502) 839-3484
fax: (502) 839-0939
www.herrick-company.com

August 24, 2026

Strand Associates, Inc.
651 Perimeter Drive, Suite 220
Lexington, KY 40517

Attention: Ms. Liz Dienst, PE

RE: Lexington-Fayette Urban County Government
Town Branch & West Hickman WWTPs
UV Disinfection Process Replacement Project
COP-19: Gutter Credit - Both Plants

Dear Ms. Dienst,

At the Owner's request, gutter installation at both the Town Branch and West Hickman WWTPs has been removed from the project scope. Herrick Company coordinated with Veteran's Contracting regarding the resulting credit. Veteran's Contracting advised that the custom-cut gutter coil has already been purchased and is nonreturnable; therefore, no material credit is available. The deleted installation labor credit is $2,900.00.

We propose to provide a **lump sum credit of <$3,190.00>.** A detailed breakdown of our proposal is provided below. We hope that you find this proposal acceptable. Should you have any questions or need any additional information, please do not hesitate to contact me.

Veteran's Labor Credit	($2,900.00)
Herrick Markup (10%)	($290.00)
Total Credit	**($3,190.00)**

Sincerely,

Jonah Donze
Project Manager

cc: Luke Zakrzewski, PE – HCI
Cody Lokits, PE - HCI
Mike Davis, PE – Strand
Emily Epperson, PE – LFUCG

HCI
HERRICK
COMPANY, INC

780 Enterprise Dr.
Lexington, KY 40510
tel: (502) 839-3484
fax: (502) 839-0939
www.herrick-company.com

August 24, 2026

Strand Associates, Inc.
651 Perimeter Drive, Suite 220
Lexington, KY 40517

Attention: Ms. Liz Dienst, PE

RE: Lexington-Fayette Urban County Government
Town Branch & West Hickman WWTPs
UV Disinfection Process Replacement Project
COP-20: Effluent Gate and Sampler Conduit Rerouting

Dear Ms. Dienst,

At LFUCG's request, please see below scope of work regarding rerouting of the Effluent Gate and Sampler Conduit at Town Branch.

Scope of work:

Sampler Circuit:
- Install approximately 220 linear feet of ¾" aluminum conduit.
- Furnish and install 6 (3) No. 12 THHN Conductors.
- Furnish and install 2 receptacles.

Effluent Gate Circuit:
- Install approximately 250 linear feet of ¾" aluminum conduit.
- Furnish and install four (4) No. 12 THHN Conductors.

Final conduit routing and receptacle locations will be coordinated with LFUCG in the field. The work above will also include new liquid tight whips. We propose to do the work above for the **lump sum price of $10,855.00.**

AEES Subcontract Proposal:	$8,615.00
Bonds + Insurance:	$430.75
Overhead + Profit	$1,809.15
Total:	**$10,855.00**

Sincerely,

Jonah Donze
Project Manager

cc: Luke Zakrzewski, PE – HCI
Cody Lokits, PE - HCI
Mike Davis, PE – Strand
Emily Epperson, PE – LFUCG

HCI
HERRICK
COMPANY, INC

780 Enterprise Dr.
Lexington, KY 40510
tel: (502) 839-3484
fax: (502) 839-0939
www.herrick-company.com

August 31, 2026

Strand Associates, Inc.
651 Perimeter Drive, Suite 220
Lexington, KY 40517

Attention: Ms. Liz Dienst, PE

RE: Lexington-Fayette Urban County Government
Town Branch & West Hickman WWTPs
UV Disinfection Process Replacement Project
COP 21: Upsizing the Water Heater Circuit/Bucket

Dear Ms. Dienst,

Description of Change

Provide all labor and materials required to upsize the circuit breaker serving the water heater at MCC-B from 20 amps to 100 amps. Work includes removal of the existing breaker, installation of the new 100-amp breaker, required terminations, and rewiring of the upsized 100 amp breaker.

We propose to perform the above work for a **lump sum price of $7,512.95**. Should you have any questions, please feel free to contact me.

Subcontractor	$6,222.00
Bonds & Insurance	$311.00
Profit and Overhead	$979.95
Total	**$7,512.95**

Sincerely,

Jonah Donze
Project Manager

cc: Luke Zakrzewski, PE – HCI
Cody Lokits, PE - HCI
Mike Davis, PE – Strand
Emily Epperson, PE – LFUCG

HCI
HERRICK
COMPANY, INC

780 Enterprise Dr.
Lexington, KY 40510
tel: (502) 839-3484
fax: (502) 839-0939
www.herrick-company.com

September 22, 2026

Lexington-Fayette Urban County Government
Division of Water Quality – Town Branch WWTP
301 Lisle Industrial Avenue
Lexington, KY 40511

Attention: Ms. Jenna Roseman

RE: Lexington-Fayette Urban County Government
Town Branch & West Hickman WWTPs
UV Disinfection Process Replacement Project
PCO-22: Additional Pallet Rack Crossbars

Dear Ms. Roseman,

As requested, please see the following change order proposal for additional pallet rack crossbars at both WWTPs, to be included in Change Order No. 2. The scope of this PCO includes:

- Furnish seventy-two (72) 36-inch pallet rack crossbars, Uline Model H-7666, at $12.00 each
- Furnish twenty (20) 48-inch pallet rack crossbars, Uline Model H-5727, at $16.00 each
- Motor freight delivery from Uline

We respectfully submit this Change Order Proposal for the **Lump Sum Price of $1,482.00** associated with furnishing the additional crossbars per PCO-22. A breakdown of material, freight, and overhead and profit is provided below:

Materials (Uline)	$1,184.00
Freight	$98.86
Overhead & Profit	$199.14
Total	$1,482.00

No additional contract time is requested. We hope that you find this proposal acceptable. Should you have any questions or require additional information, please do not hesitate to contact me.

Sincerely,

Cody M. Lokits, PE
President

cc: Jonah Donze – HCI
Luke T. Zakrzewski, PE – HCI