




TO: Mayor Linda Gorton
Urban County Council

FROM: 
Nancy B. Albright, P.E.
Commissioner, Environmental Quality
& Public Works

DATE: November 20, 2025

RE: Change order No. 2 with L-M Asphalt Partners LTD, d/b/a ATS Construction for the Salt Dome & Associated Improvements Old Frankfort Pike, original resolution No. 277-2024 and Contract No. 058-2024.

Request

The Department of Environmental Quality & Public Works requests approval of Change Order No.2 with L-M Asphalt Partners LTD, d/b/a ATS Construction, in the net amount of negative \$24,967.98, for adding 6 items to the contract and eliminating 6 items from the contract.

Items to be added: 1) Install 2" conduit with concrete backfill, 2) Provide and deliver 30' concrete barrier wall, 3) Construct asphalt pavement next to shelter, 4) Construct port-a-potty enclosure, 5) Asphalt wedge to correct low spot, and 6) Install fence on headwalls. Items to be eliminated: 1) Item 291- 4 GND IN 2" CONDUIT WITH BENTONITE BACKFILL, 2) Item 292 - 6 GND IN 2" CONDUIT WITH BENTONITE BACKFILL, 3) Item 293 - 8 GND IN 1.5" CONDUIT WITH BENTONITE BACKFILL, 4) Item 294- 8 GND IN 0.75" CONDUIT WITH BENTONITE BACKFILL, 5) Item 39 - REMEDIATION OF UNSUITABLE FOUNDATION AREA FOR STRUCTURE, and 6) Item 2012 - IMPORT AND COMPACT FILL.

Why are you requesting?

This CO serves as a "clean-up CO" to add necessary items to the project and eliminate unused items.

It was determined that the minimum conduit size was to be 2" and the back fill was to be concrete instead of bentonite. Therefore, the four conduit items are being eliminated and replaced by the one conduit item being added. Items 39 and 2012 are being eliminated because they were "allowances" incase unsuitable subgrade was encountered, which were never used. The other items are being added to improve safety and performance of the project site. The concrete barriers created bins to store loose materials, asphalt area was increased to accommodate parking and storage next to the shelter, fence was installed to screen the port-a-potty from wind and from Old Frankfort Pike, an existing water ponding issue was corrected in the pavement, and fencing was added to the top of large headwalls to provide fall protection.



What is the estimated cost in this budget year and future budget years? The current PO amount is being reduced by \$24,967.98.

Are the funds budgeted? N/A

Account Number:

1116 – 303301 -0001 - 90511 for -\$24,967.98

File Number: 1127-25

Commissioner: Albright

